

THE CITY OF PLEASANTON

January 23, 2017

ADDENDUM NO. 1

**ANNUAL SIDEWALK MAINTENANCE FOOTHILL RD ALONG
STONERIDGE MALL, PROJECT NO. 17512**

This Addendum is hereby made a part of the project contract documents. It shall be the responsibility of the general contractor to inform any affected subbidder of the content of this Addendum.

The contract documents are modified/clarified as follows:

SPECIFICATIONS:

Page 5, BID PROPOSAL

- Item Number 3 "Adjust Utility Box" update the quantity from 7 to 1.

3.	1	LS	ADJUST UTILITY BOX		
----	---	----	--------------------	--	--


PLAN SHEETS:

Plan Sheets:

Sheet C-5, 7 of 7

- Clarification that the rebar to be installed at the tree root arches shall be #4 bars on 18 -inch on center.
- Clarification that all other places the sidewalk shall be installed with #3 rebar on 16 -inch on center with fiber reinforcement per note 20 on sheet G-1, sheet 1 of 7.

All other items of work in the contract document remain unchanged. Acknowledgement and a signed copy of this Addendum shall be included in the Bid Proposal.



Stephen M. Kirkpatrick
City Engineer

ACKNOWLEDGED:

Company

Date: _____

By: _____

Title: _____